BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

NAME OF WORK: Emergency Grant (Repairs to Culverts and drains, in ward no.12, in Shettyhalli Sub-Division)

Sl. No	Description of work	Unit	Qty	Sanctioned Estimate Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	169.77	115.56	Rupees One Hundred Fifteen and Fifty Six Paise Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.86cum and fine aggregate @ 0.58cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	20.69	5070.60	Rupees Five Thousand Seventy and Sixty Paise Only
3	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregate @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	68.36	5404.32	Rupees Five Thousand Four Hundred Four and Thirty Two Paise Only
4	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1:5:3) for raft foundation, column footing, main and secondary beams. Complete as per specification and direction of Engineer-in-charge of the work.	Cum	51.33	6332.04	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL , BBMP DIVISION
BENGALURU-560 010

Executive Engineer

5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specification and direction of Engineer-in-charge of the work.	Q	8.06	69805.80	Rupees Sixty Nine Thousand Eight Hundred Five and Eighty Paise Only
6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	227.88	306.72	Rupees Three Hundred Six and Seventy Two Paise Only
7	Removing B.S. Slab Drain & Stacking.Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	1609.20	63.72	Rupees Sixty Three and Seventy Two Paise Only
8	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	603.45	83.16	Rupees Eighty Three and Sixteen Paise Only
9	Refixing stone Slabs of Drains & pointing in C.M (1:3) Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	1609.20	78.84	Rupees Seventy Eight and Eighty Four Paise Only
10	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	773.22	72.71	Rupees Seventy Two and Seventy Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL PWD DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division,